BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2016-17 Dated: 30-03-2017

MODIFIED APPROVED TENDER SCHEDULE –'B'

Item No: 12

Name of Work:-Improvements to roads and drains at Giridhamanagara of Doddabettahalli in Attur ward no 03(Change of place for Improvements to roads and drains at Muneshwaranagara 6th cross & attached road in Attur ward No:03)

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S PALAKSHAMURTHY	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no141,PWD SR 2016-17)	Cum	251.25	75.00	Rupees seventy five only
	B) above 125% of Quantity		331.55	86.29	Rupees Rupees eighty six and paise twenty nine only
2	Removing B.S slab of drain and stacking (P.No 25 I.No 5.32) A) Up to 125% of Quantity	sqm	75.93	62.00	Rupees sixty two only
	B) above 125% of Quantity		415.47	65.24	Rupees sixty five and paise twenty four only
3	Refixing stone slabs of drains and pointing in CM(1:3)(P.No 25 I.No 5.33) A) Up to 125% of Quantity	Sqm	75.93	80.00	Rupees eighty only
	B) above 125% of Quantity		415.47	79.97	Rupees seventy nine and paise ninety seven
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete **do 7.5 cms** thick(P.No 25 I.No 5.31.1) A) Up to 125% of Quantity	sqm	128.43	660.00	Rupees six hundred sixty only
	B) above 125% of Quantity		136.17	660.82	Rupees six hundred sixty and paise eighty two only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S PALAKSHAMURTHY	
				Rate	Rate in Words
5	KSRRBM400-17,Providing, laying, spreading andcompacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site,laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired dencity complete as per specifications.MORTH Specification No.406(Item no20.18,Page no157 ,PWD SR 2016-17) A) Up to 125% of Quantity	Cum	365.00	1760.00	Rupees one thousand seven hundred sixty only
	B) above 125% of Quantity		1.00	1755.17	Rupees one thousand seven hundred fifty five and paise seenteen only
6	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH Specifications No502 (ITEMNO21.6,Page no157,PWD SR 2016-17)	sqm	1560.00	25.00	Rupees twenty five only
7	KSRRB M500-19: Providing and laying bituminous concrete 40mm thick with 100/120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification NO. 509, No.165 Item No. 21.22.2.PWD SR 2016-17	Cum	62.40	7492.00	Rupees seven thousand four hundred ninety two only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S PALAKSHAMURTHY	
				Rate	Rate in Words
8	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2016-17 A) Up to 125% of Quantity	Cum	251.25	72.00	Rupees seventy two only
	B) above 125% of Quantity		331.55	71.55	Rupees seventy one and paise fifty five only

Signature of the Contractor

Executive Engineer
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.